

Two-phase flow model for energetic proton beam induced pressure waves in mercury target systems in the planned European Spallation Source

I. F. Barna¹, A. R. Imre¹, L. Rosta² and F. Mezei²

¹Atomic Energy Research Institute (AEKI) of the Hungarian Academy of Sciences,
P.O. Box 49, H-1525 Budapest, Hungary, EU

²Research Institute for Solid State Physics and Optics of the Hungarian Academy of Sciences,
P.O. Box 49, H-1525 Budapest, Hungary, EU

Received: date / Revised version: date

Abstract. Two-phase flow calculations are presented to investigate the thermo-hydraulical effects of the interaction between 300 kJ proton pulses (2 ms long, 1.3 GeV) with a closed mercury loop which can be considered as a model system of the target of the planned European Spallation Source(ESS) facility. The two-fluid model consists of six first-order partial differential equations that present one dimensional mass momentum and energy balances for mercury vapour and liquid phases are capable to describe quick transients like cavitation effects or shock waves. The absorption of the proton beam is represented as instantaneous heat source in the energy balance equations. Densities and internal energies of the mercury liquid-vapour system are calculated from van der Waals equation, and the general method how to obtain such properties is also presented. A second order accurate high-resolution shock-capturing numerical scheme is applied with different kinds of limiters in the numerical calculations. Our analysis show that even 75 degree temperature heat shocks cannot cause considerable cavitation effects in mercury in 2ms long pulses

PACS. 47.55Bx Cavitation, – 47.55Kf Multiphase and particle-laden flows – 47.90a+ Other topics in fluid dynamics

1 Introduction

One non-destructive material research method is neutron scattering. Free neutrons for neutron beams for research purposes need to be extracted from their bound states of atomic nuclei. Energetic neutron beams can be produced in fission of heavy elements (e.g. ^{235}U) or by spallation. In fission of ^{235}U 190 MeV heat is released for each extracted fast neutron while in the spallation process only about 30 MeV heat is deposited per fast neutron. The deposited heat has to be removed by cooling and it ultimately becomes a limiting thermodynamic factor for the amount of neutrons produced. As a second distinct advantage of pulsed spallation sources over continuous ones is that a larger part of the neutrons produced can be delivered to the sample in monochromatic beams. These two advantages of spallation sources make it possible to construct more powerful neutron sources with larger neutron flux than ever before. The simple goal of the planned European Spallation Source(ESS) is to provide Europe with the most powerful neutron facility. A choice of a 5 MW proton beam power at 1.3 GeV proton energy with 111 mA proton beam current and with 16.66 Hz repetition rate of 2 ms long neutron pulses will produce time average ther-

mal neutron flux density of $3.1 \times 10^{14} n/cm^2 s$ in the ESS mercury target. The proton pulse causes a thermal and a pressure shock in the target which may cause cavitation or tensile stress. The question of cavitation erosion [1] has crucial importance in the constructional planning of any spallation neutron source target facility. A detailed analysis of the planned ESS can be found elsewhere [2]. In the following study we present and analyze a one-dimensional six-equation two-fluid model which is capable to describe transients like pressure waves, quick vapour void fraction creation and annihilation which is proportional to cavitation caused by energetic proton interaction in mercury target.

Our model has a delicate numerical scheme and capable to capture shock waves and describe transient waves which may propagate quicker than the local speed of sound [3]. Most of the two-phase models have numerical methods which describes usual flow velocities.

Our model can successfully reproduce the experimental data of different one- or two-phase flow problems such as ideal gas Riemann problem, critical flow of ideal gas in convergent-divergent nozzle, column separation or cavitation induced water hammer, rapid depressurization of hot

liquid from horizontal pipes or even steam condensation induced water hammer [4].

According to our knowledge there is no real two-phase flow calculation for mercury flow system. Some timorous attempts were presented with the help of some commercial three dimensional industrial codes like Fluent or ANSYS [5,6] but the results are questionable. Some results show complete and immediate vaporization during the first proton pulse, which is contradictory to experimental observations. There are some studies for three dimensional numerical simulation of magnetohydrodynamic processes in the muon colliders mercury target. These studies take strong external magnetic fields into account [7] but consider single phase only, neglecting vaporization or condensations. The liquid phase of mercury was modeled using the stiffened politropic equation of state and the vapour phase was considered to be ideal gas. There is a literature survey on various fluid flow data for mercury from the politropic equation state [8] which can be directly applied in calculations. There are also different equations of state (EOS) available for mercury from microscopic molecular simulation [9,10] or from macroscopic theories like virial expansion [11] or from generalized van der Waals equation like the Redlich-Kwong equation [12] or the like [13]. Thermodynamical and flow properties of other liquid metals are also in the focus of recent scientific interest [14,12].

In the next sections we introduce our applied model, give a detailed analysis about phase transitions and present pressure wave results.

2 Theory

2.1 Theory of two-phase flow

There is a large number of different two-phase flow models with different levels of complexity [15,16] which are all based on gas dynamics and shock-wave theory. In the following we present our one dimensional six-equation equal-pressure two-fluid model. The density, momentum and energy balance equations for both phases are the following:

$$\frac{\partial A(1-\alpha)\rho_l}{\partial t} + \frac{\partial A(1-\alpha)\rho_l(v_l-w)}{\partial x} = -A\Gamma_g \quad (1)$$

$$\frac{\partial A\alpha\rho_g}{\partial t} + \frac{\partial A\alpha\rho_g(v_g-w)}{\partial x} = A\Gamma_g \quad (2)$$

$$\begin{aligned} \frac{\partial A(1-\alpha)\rho_l v_l}{\partial t} + \frac{\partial A(1-\alpha)\rho_l v_l(v_l-w)}{\partial x} + \\ A(1-\alpha)\frac{\partial p}{\partial x} - A \cdot CVM - A p_i \frac{\partial \alpha}{\partial x} = AC_i |v_r| v_r \\ - A\Gamma_g v_i + A(1-\alpha)\rho_l \cos\theta - AF_{l,wall} \end{aligned} \quad (3)$$

$$\begin{aligned} \frac{\partial A\alpha\rho_g v_g}{\partial t} + \frac{\partial A\alpha\rho_g v_g(v_f-w)}{\partial x} + A\alpha \frac{\partial p}{\partial x} + \\ A \cdot CVM + A p_i \frac{\partial \alpha}{\partial x} = \\ -AC_i |v_r| v_r + A\Gamma_g v_i + A\alpha\rho_g \cos\theta - AF_{g,wall} \end{aligned} \quad (4)$$

$$\begin{aligned} \frac{\partial A(1-\alpha)\rho_l e_l}{\partial t} + \frac{\partial A(1-\alpha)\rho_l e_l(v_l-w)}{\partial x} + \\ p \frac{\partial A(1-\alpha)}{\partial t} + \frac{\partial A(1-\alpha)p(v_l-w)}{\partial x} = A Q_{il} \\ - A\Gamma_g(h_f + v_l^2/2) + A(1-\alpha)\rho_l v_l g \cos\theta + E_{l,pulse}(x,t) \end{aligned} \quad (5)$$

$$\begin{aligned} \frac{\partial A\alpha\rho_g e_g}{\partial t} + \frac{\partial A\alpha\rho_g e_g(v_l-w)}{\partial x} + p \frac{\partial A\alpha}{\partial t} + \frac{\partial A\alpha p(v_l-w)}{\partial x} \\ = A Q_{ig} + A\Gamma_g(h_g + v_g^2/2) + A\alpha\rho_g v_g g \cos\theta + E_{g,pulse}(x,t) \end{aligned} \quad (6)$$

Index l refers to the liquid phase and index g to the gas phase. Nomenclature and variables are described in Table I. Left hand side of the equations contain the terms with temporal and spatial derivatives. Hyperbolicity of the equation system is ensured with the virtual mass term CVM and with the interfacial term (terms with p_i). Terms on the right hand side are terms describing the inter-phase heat, mass (terms with Γ_g vapour generation rate) volumetric heat fluxes Q_{ig} , momentum transfer (terms with C_i), wall friction $F_{g,wall}$, and gravity terms. A detailed analysis of the source terms can be found in [4]. The last term in the energy equations $E_{i,pulse}(x,t)$ represents the deposited energy from the proton beam and will be specified later on.

Two additional equations of state (EOS) are needed to close the system of equations (Eq. 1-6)

$$\rho_k = \left(\frac{\partial \rho_k}{\partial p} \right)_{u_k} dp + \left(\frac{\partial \rho_k}{\partial u_k} \right)_p du_k. \quad (7)$$

Partial derivatives in Eq. 7 are expressed using pressure and specific internal energy as an input. In the following we show how the liquid-steam table - a sixfold numerical table - ($p, T, \rho_l, u_l, \rho_g, u_g$) can be created for mercury from an arbitrary EOS. To avoid technical difficulties we do not modify (Eq. 1-6) including the used analytic EOS, just create a numerical liquid-steam table. In this manner arbitrary two phase-flow systems can be investigated with the same model in the future (e.g. lead-bismuth eutectic, liquid Li or He). Liquid metal systems can operate on low (some bar) pressure and have larger heat conductivity than water which can radically enhance thermal efficiency.

We start with the usually parameterized van der Waals EOS from

$$p = \frac{RT}{V-b} - \frac{a}{V^2} \quad (8)$$

where $R=8.314$ J/mol/K is the universal gas constant and parameters a and b are related with the critical molar volume (V_c) temperature (T_c) and pressure (p_c) of the considered fluid: $a = 9p_c V_c^2$ $b = V_c/3$ For the critical temperature and pressure of Hg the $T_c = 1733 \pm 50K$ and $p_c = 160.8 \pm 5MPa$ data were taken from [12]. T , p and V are the temperature the pressure and the volume, respectively. (We mention than in [12] the parameter $a(= 9p_c V_c^2)$ is incorrectly given.) The fluid density with the corresponding saturated vapour density can be easily determined from

the EOS with the well-known Maxwell construction. To obtain the internal energies for both phases is a bit more difficult task. We start with the second law of thermodynamics

$$du = Tds - pdV \quad (9)$$

where s is the entropy and u is the internal energy. With the Maxwell relations $(\frac{\partial T}{\partial V})_s = -(\frac{\partial P}{\partial s})_V$ we end up with the following working equation

$$du = c_V dT + \left[T \left(\frac{\partial p}{\partial T} \right)_V - p \right] dV. \quad (10)$$

The internal energy is a thermodynamical potential therefore the choice of the zero point can be defined arbitrary, we took $T = 253.14K$ which is 10 degree above the melting point of solid mercury at normal pressure. The heat capacity at constant volume c_v may in turn be calculated from the heat capacity at constant pressure c_p with the thermodynamic relation

$$c_p = c_V + T \left(\frac{\partial V}{\partial T} \right)_p^2 \left(\frac{\partial p}{\partial V} \right)_T \quad (11)$$

where $\frac{1}{V} \frac{\partial V}{\partial T} = \alpha_T$ is the thermal expansion coefficients. (To avoid further misunderstanding in this study we use α_T for the thermal expansion coefficient and α for vapour void fraction.) Polynomial fits for the temperature dependence of experimental data of heat capacity c_p and expansion coefficient α_T [17](or [8]) help us to calculate the internal energy of the liquid state. Finally, the internal energy of the corresponding gas phase has to be determined. The critical temperate of mercury is at $T_C = 1733 \pm 50K$. In the temperature range of 270-500 K (which is our recent interest) the experimental heats of vapourization data [10] can be satisfactory fitted with a linear function. With this method a two-phase liquid-steam table was constructed between 270-500 Kelvin of temperatures and 7 to $7 \cdot 10^7$ Pascal pressure.

Additional flow properties of mercury like dynamic viscosity and heat transfer coefficients are approximated with piecewise continuous temperature dependent functions from [8]. The surface tension was considered as a linear function of temperature [18].

The effect of the 300 kJ proton pulse was treated as a sudden thermal shock which means an additional source terms in both energy equations $E_{i,pulse}(x, t)$. The deposited energy of the proton beam in the mercury target is proportional to the density. With the introduction of the mixture density $\rho_m = \alpha \rho_g + (1 - \alpha) \rho_f$ the interaction between the proton-mercury two-phase flow can be further improved. According to experimental proton beam analysis the spatial energy distribution perpendicular to the propagation direction has a parabolic shape [19,20] with a diameter of 20 cm. To describe well-defined finite duration we use $\sin^2$ envelope with $\tau = 2ms$.

$$E_{g,pulse}(x, t) = \frac{\rho_g \alpha}{\rho_m} E_0 \sin^2 \left(\frac{\pi t}{\tau} \right) (1 - (x/x_s)^2) \quad (12)$$

$$E_{f,pulse}(x, t) = \frac{\rho_f (1 - \alpha)}{\rho_m} E_0 \sin^2 \left(\frac{\pi t}{\tau} \right) (1 - (x/x_s)^2) \quad (13)$$

The effective range of 1.3 GeV protons in mercury can be calculated with the Bragg theory and gives 41 cm [21]. Experimental consideration state that 47 percent of the original 5 MW beam power is absorbed in the target which is 2.37 MW. In the planned ESS facility a train of 16.66 proton pulses will come with 2ms long pulse duration and the total sum of these pulses give the 5 MW beam power. Hence, the peak power parameter E_0 has to be normalized in such a way that the spatial and time integral of $E_{i,pulse}(x, t)$ gives the absorbed 2.37 MW power of the original 5 MW beam. The system of Eqs. (1-6) represents the conservation laws and can be formulated in the following vectorial form

$$\mathbf{A} \frac{\partial \Psi}{\partial t} + \mathbf{B} \frac{\partial \Psi}{\partial x} = \mathbf{S} \quad (14)$$

where Ψ represents the vector of the independent non-conservative variables $\Psi(p, \alpha, v_f, v_g, u_f, u_g)$, $\mathbf{A}$ and $\mathbf{B}$ are the matrices of the system and $\mathbf{S}$ is the source vector of non-differential terms. These three quantities $\mathbf{A}$, $\mathbf{B}$ and $\mathbf{S}$ can be obtained from Eq. (1-6) with some algebraic manipulation. In this case the system eigenvalues which represent wave propagation velocities are given by the determinant $\det(\mathbf{B} - \lambda \mathbf{A})$. An improved characteristic upwind discretization method is used to solve the hyperbolic equation system (14). The problem is solved with the combination of the first- and second-order accurate discretization scheme by the so-called flux limiters to avoid numerical dissipation and unwanted oscillations which appear in the vicinity of the non-smooth solutions. Exhaustive details about the numerical scheme can be found in [4,3].

2.2 Liquid-vapour phase transition in the metastable region

Water boils at 100 Celsius (373.15 K) under atmospheric pressure; this is a well-known, but not entirely correct piece of the common knowledge. Boiling is usually defined (at least phenomenologically) when liquid-vapour phase transition happens not only at the already existing interfaces, but within the bulk liquid too. For water, it happens usually at the already mentioned 100 Celsius, but not always. Overheating of liquids is a phenomenon, known for every chemistry students; one can exceed the boiling point with a few degrees, without getting boiling, but then it can happen suddenly, exploding the whole amount of liquid (and often the container too) [22]. In the following, we are going to explain this phenomenon and show its importance in the cavitation of mercury. Liquid can co-exists with the vapour of the same material, without any problem. The conditions (temperature and pressure) where they co-exist are described the vapour pressure curve (also called saturation or co-existence curve). Liquid and vapour states can be described by EOS; like van der Waals. A schematic isotherm (describing pressure

and volume on a constant temperature) can be seen on Figure 1/a. The isotherm has two extrema (marked as B and D), these are the so-called spinodal points (liquid-vapour and vapour-liquid; LV and VL spinodals). Between the two spinodals, the system would be unstable, due to the negative compressibility, therefore these states (the ones on the curve between points B and D) cannot exist. The equilibrium conditions can be calculated by using the Maxwell construction: a line (parallel to the V-axis) has to be drawn in a way that the area between the isotherm and the Maxwell-line between points A and C and C and E has to be equal. Then the intersects (A and E) gives the co-existing liquid and vapour volumes (or densities) and the equilibrium pressure on the given temperature. Plotting the pressures on different temperatures, one would obtain the vapour pressure curve, like the solid line on Figure 1/b. It can be seen that points A and E are not special points of the isotherm. The liquid is not forced to boil at point A; it would be forced only at point B (where liquid phase cannot exist any more). Plotting Bs at different temperature, one would obtain the so-called liquid-vapour spinodal (dashed line on figure 1/b), the stability limit of liquid state. The vapour-liquid spinodal (dot-dash line on figure 1/b) is important when we have over-saturated vapour; we are going to neglect it here. The AB and DE parts on the isotherm are metastable; on Figure 1/b these parts are represented by the region between the vapour pressure curve and the LV spinodal. Liquid (without co-existing vapour phase) can exist in this region; even can exist under negative pressure [22,23] The real boiling happens in this metastable region. Close to the vapour pressure curve the liquid is only slightly metastable, can live for long time without nucleating vapour bubbles; far away from it (close to the spinodal) the liquid will be very metastable and cavitate (boil) with higher probability. The bubble nucleation can happen in two different ways. The heterogeneous nucleation happens when the liquid already has a nucleus, usually a tiny bubble hidden in a crevice of the wall or stuck onto a floating particle. Due to the small size (i.e. high curvature) the micro-bubble can be in equilibrium with a metastable liquid for a while, but when the temperature is too high or the pressure is too low, it will initiate boiling. The other process is the homogeneous nucleation. In that case, the initial micro-bubble will be produced by the density fluctuations of the liquid; when the fluctuation is big enough to call it "bubble", then it will initiate the boiling. In everyday life, boiling happens by heterogeneous nucleation, practically in the immediate vicinity of the vapour pressure curve. In clean liquids (like distilled water) the boiling can happen much farther. It is a well-known practice to avoid overheating (and the explosion-like boiling, following it) to put some bubble seed into the liquid, like a few pieces of sponge-like pumice (or boiling-) stones. In these nucleation processes -especially in homogeneous nucleation - time is also an important factor; a liquid can endure high overheating/stretching for a small period of time [22,23,24,25]. Therefore one cannot draw a well-defined line as nucleation limit onto the phase diagram (Figure 1); the line

drawn by us is only for demonstration. the exact location depends on the purity of liquid, the amount of external disturbances (even cosmic rays can generate bubbles in metastable liquids) and - in a great extent - on the time scale. On Figure 1/c, a magnified part of Figure 1/b (without the VL spinodal, which is irrelevant in our case) can be seen. K marks a state, where the liquid is in stable liquid phase; there is no vapour phase present. To obtain phase transition, the temperature can be increased or the pressure has to be decreased. By increasing the temperature (and keeping a constant pressure), the vapour pressure curve will be reached at point L. This is the first point, where the liquid can boil and vapour phase might appear, but in clear and undisturbed liquid, the probability of boiling here is very small. Increasing the temperature further, the nucleation limit will be reached (point M); here the phase transition will surely happen, due to heterogeneous or homogeneous nucleation, forming initially small, but continuously growing separated bubbles, which later can merge into a continuous vapour phase. When the liquid is perfectly clean, all disturbances are suppressed and the heating is very fast, etc., then this nucleation limit can be pushed very close to spinodal limit (point N), where liquid phase cannot exist any more. When the phase transition happens at the spinodal limit, one will obtain two bi-continuous phases (liquid and vapour), instead of a continuous (liquid) and an separated (vapour bubbles) one, obtained during nucleation. We should remark, that for the first appearance of the vapour phase, the system will jump back to the vapour pressure curve (which will be detected as a pressure jump). Changing the pressure at constant temperature, one would reach the vapour pressure curve at point O, then the nucleation limit at point P, finally the spinodal limit at point Q, with the same results as it happens with temperature increase. To see the extent of the effect, we will give numerical examples for water and for mercury. For water, starting from room temperature (293.15 K, 1 bar), we will reach the vapour pressure curve 373.15 K. Increasing the temperature, boiling might happen any time; the highest experimentally obtained value for overheating (i.e. point M) was around 570 K [27] giving almost 200 K overheat. The spinodal temperature for water on atmospheric pressure is still debated, it has to be located above the previously mentioned overheating limit, but certainly below the critical temperature of 1733 ± 50 K. Also for water, by decreasing the pressure, the vapour pressure curve (point O) would be reached at 0.025 bar pressure. The experimental limit of stretching is -1200 bar [27], where the estimated spinodal (depending on the model) is between -2000 and -4000 bar. For mercury at 7 bar (which is the working pressure for the mercury in the ESS) the boiling point is at 760 K, it is very far from the working temperature (which is close to room temperature, 300 K). The limit of overheating is not known, but surely below the critical temperature, which is around 1700 K. Concerning pressure drop, the vapour pressure of mercury around room temperature is almost zero (less than $2 \cdot 10^{-6}$ bar); concerning the fact that the working pressure is 7 bar, the possibility of a




Fig. 1. A subcritical isotherm of a van der Waals type fluid

pressure drop of this extent is very improbable. The measured nucleation limit of mercury at room temperature is in the -2 to -425 bar range depending on purity[26]; therefore to get bubbles, the pressure should drop from +7 bar to -2 bar for a longer period. The absolute (spinodal) limit is unknown. Although in the ESS, pressure decrease and temperature increase happens simultaneously, the working conditions are so far from the beginning of the boiling region (vapour pressure curve) that the possibility to reach it is negligible, except under special circumstances. First, there is a possibility for fast pressure oscillation after the proton pulse; the amplitude can be even 300 bar [29], which would be enough to cause cavitation. The other scenario would require gas-contamination (pre-existing gas bubbles in the mercury); in that case even a tiny pressure decrease or temperature increase can cause the growing of these micro-bubbles, mimicking boiling [29]. Non-uniform temperature and pressure distribution can cause shear stresses, which can also cause cavitation in the liquid. Finally, the proton beam itself can initiate cavitation, but only when the metastable states are already reached. We can conclude, that with a few bar pressure drop and a few tens of K temperature increase, the cavitation in the pure mercury target has low possibility. On the other hand, concerning the reported cases of cavitation in similar facilities [28] indicate, that either the conditions (T,p) might change more drastically or some phenomena, neglected by us (like pressure oscillation, shear stresses, etc.) can play more important role.

3 Results and discussion

The ESS mercury target loop is a complex facility with various pumps, heat exchangers and tanks [2]. We model however with a simple six-sided closed loop (see Figure




Fig. 2. The schematic geometrical model of the ESS target

1.) of a pipe with diameter of 5 cm and total length of 5 m. The original temperature of the mercury is $T = 300$ K with pressure of 7 bar and flow velocity of $v = 4.6$ m/s. The proton beam interacts with a mercury via a $20 \times 5 \text{ cm}^2$ window. A simple calculation shows that (47 % of 300 kJ $\Rightarrow$) 141 kJ of energy will heat up 10 kg of mercury. The temperature jump of $\Delta t = 75 \text{ K}$ is expected for ESS proton beam pulses. We applied a single pulse shot at time equal to zero and propagated Eqs. (14) to $t_{max} = 4 \times 10^{-2}$ sec. A second order numerical scheme was used with the MINMOD flux limiter [3]. For a satisfactory convergence the Courant number which measures the relative wave propagation speeds of the exact solution and the numerical solutions was set to CFL = 0.6. The pressure history of the beam-target interaction point is presented in Fig 2. After the initial pulse at $t = 1.6 \text{ ms}$ the pressure reaches its maximal value which is 50 percent higher than the original pressure. After the pulse the pressure does not fall below the initial pressure and the temperature will cool down to 300 K. The mercury vapour void fraction was originally set to zero ($\alpha = 10^{-12}$) which did not change during the time propagation allowing only "nanobubbles", too small to act as cavitation nuclei. If we consider one or two percent initial vapor void fraction (as a model for small bubbles) than a quick condensation can be observed. If we apply an elastic pipe with an elasticity of $2 \times 10^{11} \text{ N/m}^2$ Young's modulus (which are usual for steel) or/and include or exclude any kind of additional wall friction [4] for the fluid the pressure peaks will not be changed. This is clear fingerprint that the tube is still rigid enough. There is a strong indication that mercury is a non-wetting fluid on steel surface so the wall friction is negligible.

4 Summary and outlook

With the help of a one dimensional two-phase flow model we calculated the induced pressure waves and vapour void fractions in mercury induced by energetic proton beams. Our analysis showed that no vapour bubbles or cavitation effects can be seen after the first absorbed proton pulse. Further, in depth analysis is in progress to investigate geometrical effects of the mercury target loop which is a complex facility with various pumps, heat exchangers and tanks [2]. Our model can include abrupt area changes, or convergent-divergent pipe cross section changes, or even heat exchangers. We modeled however with a simple six-sided closed loop (see Figure 1.) of a pipe with diameter




Fig. 3. Time history of pressure at the point of the proton impact for the model in Fig. 2. with rigid tube walls.

of 5 cm and total length of 5 m. The original temperature of the mercury is $T = 300$ K with pressure of 7 bar and flow velocity of $v = 4.6$ m/s. The proton beam interacts with a mercury via a $20 \times 5 \text{ cm}^2$ window. A simple calculation shows that 141 kJ of energy will heat up 10 kg of mercury with a $\Delta t = 75 \text{ K}$. We applied a single pulse shot at time equal to zero and propagated Eqs. (14) to $t_{max} = 4 \times 10^{-2}$ sec. A second order numerical scheme was used with the MINMOD flux limiter [3]. The Courant number which measures the relative wave propagation speeds of the exact solution and the numerical solutions was set to CFL = 0.6. The pressure history of the beam-target interaction point is presented in Fig 3. After the initial pulse at $t = 1.6 \text{ ms}$ the pressure reaches its maximal value which is 50 percent higher than the original pressure. After the pulse the pressure does not fall below the initial pressure and the temperature will cool down to 300 K. The mercury vapour void fraction was originally set to zero ($\alpha = 10^{-12}$) which did not change during the time propagation allowing only "nanobubbles", too small to act as nucleus for cavitation. The question of the vapor void fraction, pipe elasticity or the liquid wall friction was examined also.

We would like to emphasize that further in-depth analysis is needed to clear up the question of a long pulse train. The question of different equations of state will be investigated also. As a long term interest we also planned to investigate other liquid metal (e.g. bismuth-lead eutectic or liquid lithium) or liquid helium systems which can be interesting as a cooling media for new type of nuclear reactors. Liquid metal systems can operate on low (some bar) pressure and have much larger heat conductivity than water which can radically enhance thermal efficiency.

References

1. Futakawa M., Naoe T., Tsai C.C., Kogawa H., Ishikura S., Ikeda Y., Soyama H., and Date H. H. Cavitation Erosion in Mercury Target of Spallation Neutron Source Fifth International Symposium on Cavitation (cav2003) Osaka, Japan, November 1-4, 2003

2. The European Spallation Source Project, Technical Report http://neutron.neutron-eu.net/n_ess
3. Tiselj I. and Petelin S., J. Comp. Phys. **136**, 503-521 (1997).
4. Tiselj I., Horvath A., Cerne G., Gale J., Parzer I., Mavko B., Giot M., Seynhaeve J.M., Kucienska B. and Lemonnier H. WAHA3 code manual, Deliverable D10 of the WAHALoads project, March 2004
5. 3rd High-Power Targetry Workshop, September 10-14, 2007 Bad Zurzach, Switzerland <http://asq.web.psi.ch/hptrgts/index>
6. Hiroyuki Kogawa, *et al.* Journ. of Nucl. Mat. **34**, 3178-183 (2005)
7. Samuliak R. Numerical simulation of hydro- and magneto-hydrodynamical properties in the Muon Collider target. Lecture Notes in Comp. Sci, Vol. 2331 Springer-Verlag, Berlin Heidelberg New York (2002) 391-400
8. Cords H. A Literature Survey on Fluid Data for Mercury - Constitutive Equation http://neutron.neutron-eu.net/n_ess
9. Kitamura H., Journal of Chemical Physics **126**, 134509 (2007)
10. Raabe G. and Sadus R.J. Journ. of Chem. Phys. **119**, 6691 (2003)
11. Mehdipour N. and Bousheri A., Int. Journ. of Thermophysics **18**, 1329 (1997)
12. Morita K., Sobolev V. and Flad M., Journ. of Nucl. Mat. **362**, 227-234 (2007)
13. Martynyuk M.M.Z., Fiz. Khim. **65**, 1716 (1981)
14. Mehdipour N., Boushehri A. and Eslami H., Journ. of Non-Cryst. Sol. **351**, 1333 (2005)
15. Stewart H.B. and Wendroff B., J. Comp. Phys. **56**, 363 (1984)
16. Menikoff R. and Plohr. B., Rev. Mod. Phys. **61**, 75-130 (1989)
17. Davis L.A. and Gordon R.B., Journ. Chem. Phys. **46**, 2650 (1967)
18. Jasper J.J. Phys. Chem. Ref. Data **1**, 841 (1972)
19. Ni L., Bauer G.S. and Spitzer H., Nucl. Instr. Meth. in Phys. Res. A **425**, 57 (1999)
20. Futakawa M., Kikuchi K., Conrad H. and Stechmesser H., Nucl. Instr. Meth. in Phys. Res. A **439**, 1 (2000)
21. Ziegler J.F., Biersack J.P. and Littman U., The stopping and Ranges of Ions in Matter, Pergamon Press, Oxford (1985)
22. Debenedetti P.G. 1996 Metastable Liquids: Concepts and Principles (Princeton University Press, Princeton)
23. Trevena D.H. 1987 Cavitation and Tension in Liquids (Adam Hilger, Bristol)
24. Imre A., Martiás K. and Rebelo L.P.N. J. Non-Equilib. Thermodyn. **23**, 351 (1998)
25. Imre A R, Maris H J and Williams P R (Eds.) 2002 Liquids Under Negative Pressure (NATO Science Series, Kluwer, Dordrecht)
26. Briggs L.J., J. Appl. Phys., **24**, 488-490 (1953)
27. Zheng Q., Durben D.J., Wolf G.H. and Angell C.A. Science **254**, 829 (1991)
28. Hidefumi D. and Futakawa M., Int. Journ. Imp. Eng. **32**, 118-129 (2005)
29. Taleyarkhan R.P. and Moraga F., Nucl. Eng. and Des. **207**, 181-188 (2001)

Table 1. Nomenclature used in the two-phase flow equations(Eq. 1-6.)

A	pipe cross section (m^2)
C_i	internal friction coefficient (kg/m^4)
CVM	virtual mass term (N/m^3)
e_i	specific total energy [$e = u + v^2/2$] (J/kg)
$F_{f,wall}$	wall friction per unit volume (N/m^3)
g	gravitational acceleration(m/s^2)
h_i	specific enthalpy [$h = u + p/\rho$] (J/kg)
p	pressure (Pa)
p_i	interfacial pressure $p_i = p\alpha(1 - \alpha)$ (Pa)
Q_{ig}	interf.-liq./gas heat transf. per vol. rate (W/m^3)
t	time (s)
u_i	specific internal energy (J/kg)
v_i	velocity (m/s)
v_r	relative velocity [$v_r = v_g - v_f$] (m/s)
w	pipe velocity in flow direction (m/s)
x	spatial coordinate (m)
Γ	vapour generation rate (kg/m^3)
α	vapour void fraction
ρ_i	density (kg/m^3)
θ	pipe inclination
